



# Technical Concepts and Costs of CCS (in the German North Sea)

Dr. Sven Hoog, Fichtner GmbH & Co. KG  
Beiratssitzung, Hamburg, 26.09.2023





Status of current  
activities at Fichtner



FICHTNER



Bundesanstalt für  
Geowissenschaften  
und Rohstoffe



SPONSORED BY THE




Federal Ministry  
of Education  
and Research

# GEOSTOR – finding a feasible Solution to store CO<sub>2</sub> effectively in the German North Sea


Governing aspects for designing CCS Logistics Chains:

- Storage Site location(s) - Hub location
- Storage capacity / storage volume per year
- Distances (Sources->Hub, Hub->Offshore Site)
- Transport means (low/no GHG emissions?!)
- Metocean data (water depth at site, bathymetry, wind, waves, current, soil condition)
- Sources of CO<sub>2</sub> (physical, chemical, process implications)
- Materials / components selection and availability
- Legal aspects, Contracts, HSE
- Costs (UXO, drilling, transportation, platforms, processing, temp. storage, main components, monitoring)
- Risks for all links of the Logistics Chain
- Note: CCU is also gaining Momentum (syn. Methanol, Diesel, Kerosene, LPG, LNG)




German Offshore CCS Sites under investigation in GEOSTOR

# Block Flow Diagram (BFD) for 4 Scenarios



\* Import only

# Base Case for Hub process simulation



CCS: Carbon Capture and Storage


CCU: Carbon Capture and Utilisation

CCUS: Carbon Capture, Utilisation and Storage

## Definition of Base Case for Cost Estimation:

- Import of 2 MTPA liquid CO<sub>2</sub> via small ships (7 700 m<sup>3</sup>) → Requires unloading of 258 ships per year (ca. five ships per week)
- Import of 2 MTPA liquid CO<sub>2</sub> via 32x RTCs (62 m<sup>3</sup>) → Requires unloading of 960 trains per year (ca. three trains per day)
- Export of 1 MTPA liquid CO<sub>2</sub> via Ship (23 000 m<sup>3</sup>) → Requires loading of 43 ships per year (ca. one ship per week)


# PFD\* – Rail Handling Module



## Rail Handling Module:

- Liquid CO<sub>2</sub> is unloaded from RTCs and transferred to storage tanks
  - 32 loading arms are foreseen for unloading of liquid CO<sub>2</sub>
- Gaseous CO<sub>2</sub> (displaced BOG from storage tanks) is directed to RTCs to replace liquid CO<sub>2</sub> volume with gaseous CO<sub>2</sub>
  - Vaporizer is foreseen for temporary operation if amount of BOG is not sufficient for unloading
- Buffer Tank is required to ensure that pump is primed
- Expected excess BOG production during unloading: ca. 4.84 wt.% of liquid CO<sub>2</sub> from all RTCs
- BOG is liquefied in Storage and Liquefaction Module


# PFD – Ship Handling Module: Unloading of Import Ships



## Unloading of Import Ships:

- Liquid CO<sub>2</sub> is pumped with in-tank pumps of import ship (capacity of 7 700 m<sup>3</sup>) to storage tanks
- Gaseous CO<sub>2</sub> (displaced BOG from storage tank) is directed to import ship to replace liquid CO<sub>2</sub> volume with gaseous CO<sub>2</sub>
  - Vapor return line foreseen for gaseous CO<sub>2</sub> transfer
- Expected excess BOG production during unloading: ca. 4.78 wt.% of liquid CO<sub>2</sub> from import ship
- BOG is liquefied in Storage and Liquefaction Module


# PFD – Ship Handling Module: Loading of Export Ships



## Loading to Export Ships

- Liquid CO<sub>2</sub> from storage tanks is transferred via export pump to export ship (capacity of 23 000 m<sup>3</sup>)
- Gaseous CO<sub>2</sub> (displaced BOG from export ship) is transferred to storage tanks due to high volume flow, which is connected to the Storage and Liquefaction Module
  - Vapor return line foreseen for gaseous CO<sub>2</sub> transfer
  - Blower foreseen to overcome pressure losses of vapor return line
- Expected excess BOG production during loading: ca. 4.85 wt.% of liquid CO<sub>2</sub> from export ship

# PFD – Storage & Liquefaction Module // Pipeline Module



## Storage and Liquefaction Module:

- Imported liquid CO<sub>2</sub> from rail, ship and truck is transferred to storage tanks
  - Two spherical tanks with capacity of 25 000 m<sup>3</sup> are foreseen
- Displaced BOG in storage tank is transferred to the individual modules to replace the liquid CO<sub>2</sub> in the carrier
- Excess BOG is directed to liquefaction unit
- Liquefaction is performed by multi-stage compression with intercooling


## Pipeline Module:

- Imported CO<sub>2</sub> from pipeline and CO<sub>2</sub> from storage tanks is combined in a slug catcher to meet specified export rate
- Heat exchanger necessary for liquid CO<sub>2</sub> export to meet minimum temperature for sequestration (in order to prevent formation of permafrost zone)
  - Heat integration with liquefaction unit under development

# Analysis of Scenario 2 & Scenario 4


## Pipeline from Hub to UW-Facility

Case Study: 130 km Pipeline, DN500



## Pipeline from Hub to Platform (fixed)

Case Study: 300 km Pipeline, DN500




WHP=Well Head Pressure

# Analysis of Scenario 2 & Scenario 4


## Pipeline from Hub to UW-Facility

Case Study: 130 km Pipeline, DN800



## Pipeline from Hub to Platform (fixed)

Case Study: 300 km Pipeline, DN800



# Equipment List

| ID | Rev. | DESCRIPTION         |  |        |                                    |                    | DESIGN DATA |                      |      |     |                        |     |                           |      |                                       |             |                        |                   | DIMENSIONS AND WEIGHT |             |                             |            | MATERIAL  |       |            |  | NOTES |  |
|----|------|---------------------|--|--------|------------------------------------|--------------------|-------------|----------------------|------|-----|------------------------|-----|---------------------------|------|---------------------------------------|-------------|------------------------|-------------------|-----------------------|-------------|-----------------------------|------------|-----------|-------|------------|--|-------|--|
|    |      | GEOSTOR CCS Modules | Description  | Amount | Fluid                              | Design Temperature |             | Operating Temp. [°C] |      |     | Design Press. [bar(g)] |     | Operating Press. [bar(g)] |      |                                       | Flow [m³/h] | Head @ max. flow [bar] | (Pump) Power [kW] | Electric Power [kW]   | Volume [m³] | Diameter/Width / Length [m] | Height [m] | Internals | Shell | Insulation |  |       |  |
|    |      |                     |  |        |                                    | Min                | Max         | Min                  | Norm | Max | Min                    | Max | Min                       | Norm | Max                                   |             |                        |                   |                       |             |                             |            |           |       |            |  |       |  |
| 1  |      | Hub                 | Main Storage Tanks   | 3      | LCO <sub>2</sub>                   | -46                | 50          | -                    | -30  | -   | 0                      | 22  | 13                        | 15   | 18                                    | -           | -                      | -                 | -                     | 25000       | 20,40                       | -          |           | LTCS  |            |  |       |  |
| 2  |      | Processing          | Pressure compensation evaporator (electric)                                      | TBD    | LCO <sub>2</sub> /GCO <sub>2</sub> | -46                | 50          | -                    | -30  | -   | H                      |     | H                         |      | TBD                                   | -           | -                      | TBD               | -                     | H           | H                           |            |           |       |            |  |       |  |
| 3  |      | Processing          | Booster Pumps  | 2      | LCO <sub>2</sub>                   | -46                | 50          | -                    | -30  | -   |                        | 30  |                           | 25   |                                       | 1060        | TBD                    | TBD               | -                     | -           |                             |            |           |       |            |  |       |  |
| 4  |      | Transportation      | Export Pumps   | TBD    | LCO <sub>2</sub>                   | -46                | 50          | -                    | -30  | -   | H                      |     | H                         |      | 1060                                  | H           | bis 11MW               | -                 | -                     |             |                             |            |           |       |            |  |       |  |
| 5  |      | Harbour/Jetty       | Marine Loading Arms (LYL-configuration), Large Ships up to 23 000 m <sup>3</sup> | 3      | LCO <sub>2</sub> /GCO <sub>2</sub> | -46                | 50          | -                    | -30  | -   |                        |     |                           |      | LCO <sub>2</sub> 1418 per loading arm |             |                        |                   |                       | 0,3238 / 80 |                             |            |           |       |            |  |       |  |
| 22 |      | Harbour/Jetty       | Marine Loading Arms, Medium Ships up to 7 700 m <sup>3</sup>                     | 2      | LCO <sub>2</sub> /GCO <sub>2</sub> |                    |             |                      |      |     |                        |     |                           |      | LCO <sub>2</sub> 1252 per loading arm |             |                        |                   |                       | 0,406 / 80  |                             |            |           |       |            |  |       |  |

The Equipment List (selected view) summarizes main Components of the overall facility as Basis for the Cost estimate


# Layout planning (updated)

## Main Building Blocks


- A Jetty or Berth Quay
- Storage in (spherical) storage Tanks
- Process Plant incl.
  - Entrance with roads to the plant
  - Workshop, laboratory and admin. building
  - Gas conditioning trains
  - Compressor, chiller and pump trains
- Pipeline connecting Jetty and Tanks
- Truck loading/unloading Station
- Train loading/unloading Station
- Import Pipeline to the Hub
- Export Pipeline to the subsea storage Site

## Aim is

- to evaluate the overall feasibility
- to define an effective footprint, small area is preferred
- to define the base for the cost estimation



# Layout planning (modular approach)



CO<sub>2</sub> handling is organized in five Main Modules:

1. Rail Handling Module
2. Truck Handling Module
3. Pipeline Module
4. Storage and Liquefaction Module
5. Ship Handling Module (not shown here)

The Storage and Liquefaction Module is interfacing with all other Modules

- All produced Boil-Off Gas (due to heat ingress and pressure losses in pipes and vessels) is handled centralized at the Storage and Liquefaction Module
- Excess BOG is liquefied to minimize CO<sub>2</sub> losses

# Risk Assessment (HAZID)

| Risk Assessment/<br>Risikoanalyse<br>GEOSTOR   | Keyword / Schlagwort | Applicable<br>for/<br>Anwendbar<br>auf   | Cause / Comment<br>Ursache / Kommentar  | Consequence / Konsequenzen   | Probability/<br>Wahrscheinlichkeit | Existing<br>safeguards/<br>existierende<br>Sicherheitsregel |                       |                         |                         |                                 |                 | Mitigation measure / Minderungsmaßnahme | Action / Maßnahme |    |     |  |  |
|--|----------------------|--|---|--|------------------------------------|---|-----------------------|-------------------------|-------------------------|---------------------------------|-----------------|---|-------------------|----|-----|--|--|
|  |                      |  |   |  |                                    | Safety/<br>Sicherheit                                       | Health/<br>Gesundheit | Environment /<br>Umwelt | Reputation /<br>Ansehen | Economy /<br>Wirtschaftlichkeit | Risk/<br>Risiko |   |                   |    |     |  |  |
| <b>Section 1: Legislative and normative Risks / Gesetzgeberische und normative Risiken</b> |                      |  |   |  |                                    |   |                       |                         |                         |                                 |                 |   |                   |    |     |  |  |
| Laws, Rules and Regulations / Gesetze, Vorschriften und Regelungen                         | TA Lärm              | All  | Zahlreiche regelmäßige Transporte per Landfahrzeug oder Schiff zu Tage und in der Nacht.  | Lärmbelastungen hängen von Frequenz und Typ der Fahrzeuge ab. Möglicher Show-Stopper bei Überschreitung zulässiger Grenzwerte. | Unlikely                           | 2   | Minor                 | 0                       | Serious                 | 2                               | Serious         | 2                                       | Serious           | 2  | 4   | Nutzung von mögl. geräuscharmen Transportfahrzeugen. Auch ein Pipeline-Netzwerk ist vorgesehen.  | Gutachten ist zu erstellen.  |
|  | Hub                  | Hub  | Arbeit rotierender Maschinen (Kühler, Kompressoren, Pumpen).  | Lärmbelastung übersteigt geltende Grenzwerte. Maschinen müssen ggf. eingehaust werden.   | 0                                  | 0   | 0                     | 0                       | 0                       | 0                               | 0               | 0                                       | 0                 | 0  | 0   |  |  |
| TA Luft  | All                  | Zahlreiche regelmäßige Transporte per Landfahrzeug oder Schiff zu Tage und in der Nacht. | Lufschadstoffbelastung hängen von Frequenz und Typ der Fahrzeuge ab. Möglicher Show-Stopper bei Überschreitung zulässiger Grenzwerte. | Lufschadstoffbelastung übersteigt geltende Grenzwerte. Maschinen müssen ggf. abgasnachbehandelt werden.                        | Most likely                        | 16  | Minor                 | 0                       | Serious                 | 2                               | Serious         | 2                                       | Serious           | 16 | 256 | Nutzung von mögl. Abgasarmen Transportfahrzeugen. Auch ein Pipeline-Netzwerk ist vorgesehen.   | Gutachten ist zu erstellen.  |
|  | Hub                  | Hub  | Arbeit rotierender Maschinen (Kühler, Kompressoren, Pumpen).  |  | 0                                  | 0   | 0                     | 0                       | 0                       | 0                               | 0               | 0                                       | 0                 | 0  | 0   |  |  |
| Einhaltung des Standards und Normen, (TRGS, TRBS, TRAS, TRWS,...) BImSchG                  | All                  | Arbeit mit Gefahrenstoffen (CO2)   |   |  | Probable                           | 8   | Minor                 | 0                       | Minor                   | 0                               | Minor           | 0                                       | Very serious      | 4  | 32  |  |  |
| BImSchG  | All                  | Lagerung / Hantierung von Gefahrenstoffen in Größenordnung unterliegt dem BImSchG        | Erstellung zahlreicher Dokumentationen zu Sicherheit, Brandschutz, Ex-Schutz werden benötigt und liegen nicht geeignet vor.           | Behörden werden nicht früh genug kontaktiert. Gutachten legen nicht geeignet vor.  |                                    |   |                       |                         |                         |                                 |                 |   |                   |    |     | Ein erfahrener Planer sollte dringend beauftragt werden. Kenntnis der Materie, der zuständigen Behörden und ein Netzwerk von benötigten Gutachtern sind vorteilhaft. | Frühere Ausschreibung und Beauftragung des Planungsbüros. Frühere Identifikation und Information der zuständigen Behörden (Scoping Termin) |
| BetrSchV   | Staff                | Der verantwortliche Umgang bei Transport und Hantierung ist sicherzustellen              | Bei Missachtung wird keine Betriebsgenehmigung erteilt  |  | 0                                  | 0   | 0                     | 0                       | 0                       | 0                               | 0               | 0                                       | 0                 | 0  | 0   |  |  |
| Bauordnung   | Hub                  | Einhaltung benötigter Gebäudeabstandsflächen,  | Verfügbare Baufläche nicht ausreichend  |  | 0                                  | 0   | 0                     | 0                       | 0                       | 0                               | 0               | 0                                       | 0                 | 0  | 0   |  |  |
| Brandschutz  | All                  | Arbeiten mit brennbarer und explosiven Stoffen   |   |  | 0                                  | 0   | 0                     | 0                       | 0                       | 0                               | 0               | 0                                       | 0                 | 0  | 0   |  |  |
| AwSV   | All                  | Bestandteil des BImSchG-Verfahrens. Leckage von grundwassergefährdenden Stoffen.         | Verunreinigung des Bodens und des Grundwassers  |  | 0                                  | 0   | 0                     | 0                       | 0                       | 0                               | 0               | 0                                       | 0                 | 0  | 0   | Einplanung von Auffangwannen unter mögl. Leckageorten (Flanschen, Leitungskupplungen, Schmiernittelbereichen)  |  |

## Risk Register (selected view of initial assessment)


### Risk Categories

The Risk Register lists identified Causes and Effects as Basis for a HAZID. The initial status is answered by a mitigation round.

The Risks result from multiplying

**Risk = Probability of occurrence x Severity (here: for 5 fields)**

In a later stage an HAZOP also allows consideration of operational Risks



Resulting Risk Matrix (initial and after mitigation measures, example)

# Next Steps

## Technology

- Communication with AP 2 for required Flow Regimes to reach injection goals – **yet to come**
- Fine tuning of HYSYS Simulations to get the correct inputs for the Heat and Material Balances - ongoing
- Fine tuning of Block Flow Diagrams (BFD, for considered Options) - OK
- Preparation of simplified Process Flow Diagrams (PFD) - OK
- Finalization of Equipment Lists - ongoing
- Preparation of Electrical Load Lists - ongoing

## Costs

- Started, based on equipment list
- Development of a cost model
- Implementation of selected technology into the cost model
- Goal: Cost per stored ton of CO<sub>2</sub> for each considered Scenario

A photograph of an underwater environment. In the foreground, there are numerous large, light-colored, rounded stones or boulders resting on a sandy bottom. Sunlight filters down from the surface, creating bright highlights on the stones and casting deep shadows in the crevices between them. In the background, more of the rocky seabed extends towards the horizon. A few small, dark, indistinct shapes, possibly fish or marine life, can be seen swimming among the rocks.

Many thanks for  
your attention!

Contact:      Sven.Hoog@fichtner.de;  
                 Achim.Stuible@fichtner.de

<https://geostor.cdrmare.de>

